



**SANTA ROSA COUNTY  
PUBLIC WORKS DEPARTMENT**

STEPHEN FURMAN  
Director  
stephenf@santarosa.fl.gov

6075 Old Bagdad Highway | Milton, Florida 32583

**MEMORANDUM**

TO: Tony Gomillion, County Administrator  
FROM: Stephen Furman, Public Works Director   
DATE: Oct. 18, 2016  
SUBJECT: District 2 Road Resurfacing Recommendations

**RECOMMENDATION**

Discussion of approval of resurfacing the following roads in District 2 at an estimated cost of \$230,400.00:

- Fortune Road (from Carl Booker Rd. to 2,145 feet to the east), \$23,200.00
- Pauline Street, \$28,400.00
- Douglas Street, \$10,300.00
- Carl Booker Road (from Carl Booker Rd. to Fortune Rd.), \$44,400.00
- Leopard Road, \$48,000.00
- Glenview Road, \$22,900.00
- Glenwood Drive, \$16,600.00
- Bliss Way (2,300 feet in two separate sections), \$31,500.00
- Dickerson City Road (western 475 feet), \$5,100.00

**BACKGROUND**

The District 2 roads being recommended for resurfacing score high on our Road Rating criteria and/or score close enough to adjacent roadways that warrant resurfacing to recommend them for resurfacing at the same time.

## District Two Resurfacing Recommendations

<p><b>Pauline Street</b>  2090' x 20'  105 tons SAHM @ 45 lbs. per yd<sup>2</sup>  279 tons SP-9.5 @ 120 lbs. per yd<sup>2</sup>  12 tons SP-9.5 for driveway  10 tons SP-9.5 for intersection</p>	<p><b>\$28,375.90</b></p>
<p><b>Douglas Street</b>  960' x 19'  127 tons SP-9.5 @ 125 lbs. per yd<sup>2</sup>  10 tons SP-9.5 for driveway  5 tons SP-9.5 for intersection</p>	<p><b>\$10,280.80</b></p>
<p><b>Carl Booker Road (from Hickory Hammock to Fortune Rd.)</b>  2500' x 23'  144 tons SAHM @ 45 lbs. per yd<sup>2</sup>  480 tons SP-12.5 @ 150 lbs. per yd<sup>2</sup>  10 tons SP-12.5 for driveway  10 tons SP-12.5 for intersection</p>	<p><b>\$44,378.80</b></p>
<p><b>Fortune Road (from Carl Booker to Fortune Rd.)</b>  2145' x 18'  322 tons SP- 12.5 @ 150 lbs. per yd<sup>2</sup>  5 tons SP-12.5 for intersection</p>	<p><b>\$23,118.90</b></p>
<p><b>Leopard Road</b>  3540' x 18'  160 tons SAHM @ 45 lbs. per yd<sup>2</sup>  531 tons SP- 12.5 @ 150 lbs. per yd<sup>2</sup>  6 tons SP-12.5 for driveway</p>	<p><b>\$47,997.90</b></p>
<p><b>Glenview Road</b>  1805' x 16'  64 tons SAHM @ 45 lbs. per yd<sup>2</sup>  219 tons SP-9.5 @ 120 lbs. per yd<sup>2</sup>  24 tons SP-9.5 for driveway</p>	<p><b>\$ 22,892.30</b></p>

**Glenwood Drive** \$16,629.80  
1310' x 19'  
62 tons SAHM @ 45 lbs. per yd<sup>2</sup>  
166 tons SP- 9.5 @ 120 lbs. per yd<sup>2</sup>  
10 tons SP-9.5 for intersection

**Bliss Way (*resurface two different places.*)** \$31,498.80  
2300' x 18'  
104 tons SAHM @ 45 lbs. per yd<sup>2</sup>  
345 tons SP- 12.5 @ 150 lbs. per yd<sup>2</sup>

**Dickerson City Road (*from Garcon Point Rd 475 ft*)** \$5,019.70  
475' x 18'  
71 tons SP- 12.5 @ 150 lbs. per yd<sup>2</sup>

***Total Estimated Cost*** **\$230,192.90**